



Republic of the Philippines
Department of Education
Cordillera Administrative Region
SCHOOLS DIVISION OF BAGUIO CITY
REQUEST FOR QUOTATION

Standard Form No.:SF-GOOD-60
Revised on: May 24, 2004
Standard Form Title: Request for Quotation

Supplier:	Requesting Unit:N.Tibangay/SGOD
Address:	PR No.:2024-11-352
Telephone No.:	Quotation No.: 2024-12-321
e-Mail:	Date: December 5, 2024
Delivery Period:	ABC: 147,077.85
Date Received by the Supplier:	

Please quote your lowest price on the item/s listed, subject to the General Conditions below, stating the shortest time of delivery and **submit your quotation in a sealed envelope** duly signed by your representative not later than December 10, 2024 @ 9:00 am

Failure to submit this on or before the due date aforesated will be a ground for disqualification.

(on leave)

CARMEL F. MERIS

OIC-Assistant Schools Division Superintendent
Chairman, Bids and Awards Committee

NIÑO M. TIBANGAY
BAC Vice Chairperson

REQUIREMENTS:

1. Mayor's / Business permit
2. PhilGEPS registration number or certificate
3. Omnibus Sworn Statement if above 50,000.00
4. Income/Business Tax Return 500,000.00 and above

Note:

- ✓ Submit RFQ together with the requirements.
- ✓ All entries must be typewritten or legibly written.
- ✓ Delivery period within _____ Calendar Days.
- ✓ Price validity shall be for a period of 30 Calendar Days.

Item No.	Qty.	Unit	Item Description	ABC	Unit Price	Total Price
1	1.00	lot	Mobilization/Temporary Structures, Utilities and Services/Demobilization	468.59 x 1 = 468.59		
2	1.00	lot	Safety and Health	1548 x 1 = 1548		
3	1.00	lot	Project Billboard	4891.6 x 1 = 4891.6		
4	200.00	sets	Scaffolding Rental	60 x 200 = 12,000		
5	68.79	sq m	Removal of Roofing Sheets	9.00 x 68.79 = 619.11		



Republic of the Philippines
Department of Education
Cordillera Administrative Region
SCHOOLS DIVISION OF BAGUIO CITY

6	98.40	lm	G.I. Long-Span Roofing, Corrugated, Pre-Painted, 1220mm x 0.5mm	$624.00 \times 98.40 = 61,401.6$		
7	5.00	pc	Removal of Ridge Roll	$18.00 \times 5 = 90$		
8	12.00	pc	Removal of Flashing	$18.00 \times 12 = 216$		
9	10.00	pc	Removal of Gutter	$18.00 \times 10 = 180$		
10	1,000.00	pc	Teckscrew 2-1/2"	$2.40 \times 1,000 = 2,400$		
11	247.00	pc	Blind Rivets	$1.62 \times 247 = 400,14$		
12	5.00	pc	G.I. Ridge Roll, Preformed, Pre-Painted, 0.610m x 2.440m x 0.6mm BMT	$648.00 \times 5 = 3,240$		
13	6.00	pc	G.I. Flashing, Preformed, Pre-Painted, 0.610m x 2.440m x 0.6mm BMT	$960.00 \times 6 = 5,760$		
14	96.50	l.m	Ceiling Eaves (use spandrel 7" width)	$135.00 \times 96.50 = 13,027.50$		
15	2.00	pcs	1.5"x1.5" angle bar	$1261.00 \times 2 = 2,522$		
16	3.00	pcs	C-purlin (2" x 10") metal fascia board	$1573.00 \times 3 = 4,719$		
17	1.00	kg	3" Common nail	$108.00 \times 108 = 108$		
18	1.00	gal	Primer, Red Oxide	$546.00 \times 1 = 546$		
19	1.00	gal	Quick Drying Enamel	$1133.00 \times 1 = 1,133$		
20	1.00	pc	2" paint brush	$60.00 \times 1 = 60$		
21	2.00	pcs	2"x3" C-purlin	$663.00 \times 2 = 1,326$		
22	15.00	pc	Metal Carrying Channel (12mm x 38mm x 5m x 0.8mm thk)	$182.00 \times 15 = 2,730$		
23	2.00	kg	welding rod	$195.00 \times 2 = 390$		
24	1.00	kg	1" concrete nail	$130.00 \times 1 = 130$		
25	5.00	pcs	Wall angle	$156.00 \times 5 = 780$		
26	5.00	pcs	Facia Cover	$260.00 \times 5 = 1,300$		
27	5.00	pcs	End moulding	$234.00 \times 5 = 1,170$		
28	5.00	pc	Gutter, Pre-Painted, Ordinary, 0.610m x 2.440m x 0.6mm thk	$960.00 \times 5 = 4,800$		
29	6.00	L	Roof Sealant	$564.00 \times 6 = 3,384$		



Republic of the Philippines
Department of Education
Cordillera Administrative Region
SCHOOLS DIVISION OF BAGUIO CITY

30	12.00	pc	PVC Sanitary Pipe 3"Ø x 3.0m, s1000	648.00 x 12 =7,776		
31	8.00	pc	PVC Sanitary Elbow 90°x 3"Ø	62.40 x 8 = 499.20		
32	2.00	pc	PVC Sanitary Wye 3" x 3"	106.80 x 2 =213.6		
33	2.00	pc	PVC Sanitary Elbow 1/8 x 3"Ø	50.40 x 2 = 100.8		
34	1.00	can	PVC Cement	144.00 x 1 = 144		
			***Note: inclusive of labor cost in each item -5% VAT -see attached plans for reference		TOTAL	
Purpose: Procurement of materials and replacement services for the replacement of roofing of the three storey building at Pinget National High School						

After having carefully read and accepted your General Conditions, I/We quote you on the item at prices noted above.

Signature over Printed Name

Tin

Date/Telephone No.

Canvassed by:




PROGRAM OF WORKS
BILL OF QUANTITIES
QRF 2023-SAVINGS

School : PINGET NATIONAL HIGH SCHOOL	Date: April 29, 2024
School I.D 305286	Budget Allocation: PHP 147,077.85
Region CAR	Engineering and Administrative Overhead: PHP 0.00
Division BAGUIO CITY	Approved Budget for the Contract: PHP 147,077.85
Project Title :	Completion Period: 20 Calendar days
: REPLACEMENT OF ROOFING OF THE THREE (3) STOREY BUILDING	Minimum Required Manpower:
	Foreman
	Tinsmith
	Helper
Location : Upper Pinget, Baguio City	Minimum Required Equipment:
	Drill Bit
	Riveter

ITEM NO.	Item Description	% of Total	Unit	Quantity	Total Cost	Remarks
	I. DIRECT COST					
	GENERAL REQUIREMENTS	5.05%	lot	1.00	7,434.00	
8.0000	Roofing Works	90.18%	sq.m.	137.41	132,640.14	
	Sub-Total				140,074.14	
	II. INDIRECT COST 22% of (I-Gen. Rqmnts.)					
	Overhead Expenses (8%) of (I-Gen. Rqmnts.)	0.00%				
	Contingencies (3%) of (I-Gen. Rqmnts.)	0.00%				
	Miscellaneous (1%) of (I-Gen. Rqmnts.)	0.00%				
	Contractor's Profit (10%) of (I-Gen. Rqmnts.)	0.00%				
	Sub-Total					
	III. TAX 5% of (I+II)					
	Sub-Total	4.76%			7,003.71	
	IV. TOTAL CONSTRUCTION COST (I + II + III)	100.00%			147,077.85	

Prepared by:


ALEXANDER T. TUMAPANG
 Engineering Assistant


Checked by:


JORDAN B. GAS-IB
 Engineer III

Recommending Approval:


NIÑO M. TIBANGAY
 Chief, SGOD

Approved by:


SORAYA T. FACULO PhD, CESO VI
 Assistant Schools Division Superintendent
 OIC - Office of the Schools Division Superintendent



PROGRAM OF WORKS
DETAILED COST ESTIMATE

PROJECT : REPLACEMENT OF ROOFING OF THE THREE (3) STOREY BUILDING
 SCHOOL : PINGET NATIONAL HIGH SCHOOL
 LOCATION : UPPER PINGET, BAGUIO CITY
 OWNER : DEPARTMENT OF EDUCATION

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT COST		TOTAL COST		GRAND TOTAL
				MATERIAL	LABOR	MATERIAL	LABOR	
	GENERAL REQUIREMENTS	lot	1.00					
	Mobilization/Temporary Structures, Utilities and Services/Demobilization	lot	1.00	820.00	548.00	820.00	548.00	1,368.00
	Safety and Health	lot	1.00	1,548.00	0.00	1,548.00	0.00	1,548.00
	Project Billboard	lot	1.00	3,250.00	1,268.00	3,250.00	1,268.00	4,518.00
	Sub-total							7,434.00
3.00	Roofing Works	sq.m.	137.41					
8.0100	Removal of Roofing Sheets	sq m	137.41	0.00	9.00	0.00	1,236.69	1,236.69
8.0600	G.I. Long-Span Roofing, Corrugated, Pre-Painted, 1220mm x 0.5mm	lm	143.00	520.00	104.00	74,360.00	14,872.00	89,232.00
8.0200	Removal of Ridge Roll	pc	5.00	0.00	18.00	0.00	90.00	90.00
8.0300	Removal of Flashing	pc	12.00	0.00	18.00	0.00	216.00	216.00
8.0400	Removal of Gutter	pc	10.00	0.00	18.00	0.00	180.00	180.00
8.1000	Teckscrew 2-1/2"	pc	2,000.00	2.00	0.40	4,000.00	800.00	4,800.00
8.1100	Blind Rivets	pc	600.00	1.35	0.27	810.00	162.00	972.00
8.0700	G.I. Ridge Roll, Preformed, Pre-Painted, 0.610m x 2.440m x 0.6mm BMT	pc	5.00	540.00	108.00	2,700.00	540.00	3,240.00
8.0800	G.I. Flashing, Preformed, Pre-Painted, 0.610m x 2.440m x 0.6mm BMT	pc	12.00	800.00	160.00	9,600.00	1,920.00	11,520.00
8.1400	Gutter, Pre-Painted, Ordinary, 0.610m x 2.440m x 0.6mm thk	pc	10.00	800.00	160.00	8,000.00	1,600.00	9,600.00
8.1300	Roof Sealant	L	5.00	470.00	94.00	2,350.00	470.00	2,820.00
12.0600	PVC Sanitary Pipe 3"Ø x 3.0m, s1000	pc	12.00	540.00	108.00	6,480.00	1,296.00	7,776.00
12.1000	PVC Sanitary Elbow 90° x 3"Ø	pc	8.00	52.00	10.40	416.00	83.20	499.20
12.1700	PVC Sanitary Wye 3" x 3"	pc	2.00	89.00	17.80	178.00	35.60	213.60
12.1400	PVC Sanitary Elbow 1/8 x 3"Ø	pc	2.00	42.00	8.40	84.00	16.80	100.80
12.3000	PVC Cement	can	1.00	120.00	24.00	119.85	24.00	143.85
	Sub-total							132,640.14
I.	DIRECT COST							140,074.14
II.	INDIRECT COST 22% of (I - Gen. Req.)							0.00
III.	TAX 5% of (I + II)							7,003.71
IV.	TOTAL CONSTRUCTION COST (I + II + III)							147,077.85

Prepared by:

ALEXANDER T. TUMAPANG
 Engineering Assistant

Recommending Approval:

NIÑO M. TIBANGAY
 Chief, SGOD

Checked by:

JORDAN B. GAS-IB
 Engineer III

Approved by:

SORAYA T. FACULO Phd, CESO VI
 Assistant Schools Division Superintendent
 OIC - Office of the Schools Division Superintendent



DepEd

REPAIR OF ROOFING OF THE THREE STOREY CLASSROOM BUILDING AT PINGET NATIONAL HIGH SCHOOL

UPPER DRAWING SET

PROJECT & LOCATION:

PREPARED BY:

ALEXANDER T. TUMAPANG
Engineering Assistant

CHECKED & REVIEWED BY:

ENGR. JOE DAN B. GASIB
Engineering III

RECOMMENDING APPROVAL:

NINO M. T. DANGAY
Chief SCOD

APPROVED:

SORAY T. FACILDAN, CESO VI
Assistant Schools Division Superintendent
O/C-Office of the Schools Division Superintendent

SHEET CONTENTS:

AS SHOWN

1/1

